

ADDENDUM NO. 1

JULY 10, 2024

**RIVER ROAD WASTEWATER TREATMENT PLANT
BELT PRESS BUILDING DEMOLITION**

A/E PROJECT NO. 20-2183Y
QUOTE NO. 2024.25

ST. JOHN THE BAPTIST PARISH
OWNER

MEYER ENGINEERS, LTD.
ENGINEER AND ARCHITECT

NOTICE TO BIDDERS:

This Addendum shall be considered part of the Contract Documents for the same above-mentioned project as though it had been issued at the same time and incorporated integrally therewith. Where provisions of the following supplementary data differ from those of the original Contract Documents, this Addendum shall govern and take precedence.

Acknowledge receipt of the addendum by inserting its number on the Bid Form of the Bid Documents. Failure to do so will cause the bid response to be rejected.

Bidders are hereby notified that they shall make any necessary adjustments in their estimates on account of this Addendum. It will be construed that each Bidder's proposal is submitted with full knowledge of all modifications and supplemental data specified herein.

QUESTIONS:

- AD1.1 Q1: On sheet D101, there are (8) concrete columns that the sludge press rest on. Are these columns to be removed as well?
- A1: *Yes, the columns referenced are included in the demolition, they should be flush with the existing concrete slab. For reference use addendum item numbered AD1-2.*
- Q2: The existing sludge in the equipment. Can we dump that at another location on site?
- A2: *Refer to Project Manual Section 013543.13 – Environmental Procedures for Hazardous Materials, Part 3 – Execution, Article 3.3 - “Additional Clean-Up and Disposal Requirements.”*
- Q3: The fiberglass tank has about 300 gallons of some type of liquid/ substance. If we are to dispose of that, please identify what the liquid is and where do we need to dispose of it?
- A3: *Refer to Project Manual Section 013543.13 – Environmental Procedures For Hazardous Materials, Attachment – Hazardous Material Survey Report, Paragraph – Findings, Subparagraph - “Commercial and Industrial Equipment.”*
- Q4: Any of the equipment that is being removed to be salvaged for owner?
- A4: *No. Refer to Project Manual Section 013543.13 – Environmental Procedures for Hazardous Materials, Part 3 – Execution, Article 3.2.10 – Scrap Metal for additional information concerning scrap metal.*

